

## Planning Permit Application Form

455 County Center, 2nd Floor • Redwood City CA 94063 Mail Drop: PLN 122 • TEL (650) 363-4161 • FAX (650) 363-4849 www.co.sanmateo.ca.us/planning

2016-0001 PLN: Applicant: PHILOMENALLC Mailing Address: 1580 LAVRELST, STE. C. San M Plenning and Build Bounty SAN CARLOS, CA 94070 450,394.8615 Phone, W: E-mail Address: TCCTCAPEYPEALTY. COM FAX: 650394: 8614 Name of Owner (1): SAME AS ABOVE Name of Owner (2): Mailing Address: Mailing Address: Zip: Phone,W: Phone, W: H: H: E-mail Address: E-mail Address: Project Location (address): NO ADDRESS Assessor's Parcel Numbers: 048-054 -VACANT LOT, HALF HOW BAY Zoning: Parcel/lot size: 5,320 SF (Square Feet) List all elements of proposed project: (e.g. access, size and location, primary and accessory structures, well, septic, tank) NEW SINGLE-FAMILY HOME; 2,588 SOFT (INCLIDING PORCHAPATIO); CRAFTSMEN STYLE; 3 BED/2.5 BATHS Describe Existing Site Conditions/Features (e.g. topography, water bodies, vegetation): Describe Existing Structures and/or Development: VACANT LOI We hereby certify that the information stated above and on forms, plans and other materials submitted herewith in support

We hereby certify that the information stated above and on forms, plans and other materials submitted herewith in support of the application is true and correct to the best of our knowledge. It is our responsibility to inform the County of San Mateo through our assigned project planner of any changes to information represented in these submittalls.

Owner's signature: (1 // Clay, maryer Albertan (C)

Applicant's signature: (1/h) le num - M'hom LCC

# Application for Design Review by the County Coastside Design Review Committee

#### Planning and Building Department

County Government Center = 455 County Center = Redwood City CA 94063 Mail Drop PLN 122 = 650 • 363 • 4161 = FAX 650 • 363 • 4849

Permit #: PLN 2016 -000 44

Other Permit #: 1. Basic Information Applicant: Owner (if different from Applicant): Name: PHILOMENA, LLC Name: Address: 1580 LAUREL ST, STE. C Address: SAN CAPLOS, CA Zip: 94070 Zip: Phone, W: 650.394.8615 H: Phone,W: caregreaty com Email: JAN 1 4 2016 Architect or Designer (if different from Applicant): Name: STEVE KELLOND San Mateo County Address: 14510 BIG BACIN WAY#205, SAPATOGA Zip: 950170nd Building Department Email: Stevic Kellondavanitects. com 2. Project Site Information Project location: Site Description: 8-054-120 Vacant Parcel Address: NO ADDRESS YET Existing Development (Please describe): Zip: 94019 HALF MOON BASY Zoning: Parcel/lot size: 5.32.0 sq. ft. 3. Project Description Project: Additional Permits Required: New Single Family Residence: 2441 Certificate of Compliance Type A or Type B Addition to Residence: Coastal Development Permit Other: \_ Fence Height Exception (not permitted on coast) Grading Permit or Exemption Home Improvement Exception Non-Conforming Use Permit Off-Street Parking Exception □ Variance

Fill in Blanks:	Material	Color/Finish  (If different from existing, attach sample	Check if matches existing
	/	(ii dillerent from existing, attach sampi	e)
a. Exterior walls	Atricac Hands siching	Creyluhide	
b. Trim	- Wood,	white	
c. Windows	_wood,	whide	
d. Doors		staile (	
e. Roof	compesition shiple	Black/bref	
f. Chimneys			
g. Decks & railings	wood	Stain	
h. Stairs			
i. Retaining walls			
j. Fences	wood	stain	
k. Accessory buildings			
I. Garage/Carport	2 CAR	white:	
including the required find applicable to the location	in, the County must determine that this prolings that the project does conform to the of the project pursuant to Section 6565.10 t's Statement of project compliance with st	standards and guidelines for design i	review
6. Signatures			
I hereby certify that the inf support of the application San Mateo through my ass	formation stated above and on forms, plan is true and correct to the best of my know signed project planner of any changes to i	ledge. It is my responsibility to inform nformation represented in these subr	the County of nittals.
1/12/11/2		2/16	

#### Planning and Building Department

#### Application for a Coastal Development Permit

455 County Center , 2nd Floor • Redwood City, CA 94063 Mail Drop: PLN 122 • TEL (650) 363-4161 • FAX (650) 363-4849

Companion Page

JAN 1.4 2013

ILOMENA, LLC Applicant's Name:

San Mateo County

WOOD

NA

2014-00014 Primary Permit #

#### 1. Instructions

g. Retaining Walls

i. Storage Tanks

h. Fences

Please fill out the general Planning Permit Application Form and this form when applying for a Coastal Development Permit.

ויסט וווטגנ מוצט צעטוווונ מוו וני	erns indicated on the checklist found	on the reverse side of the Planning Pern	nit Application Form.
2 Basic Infor	mation		
listed?	ant own any adjacent property not	Have you or anyone else previously application of San Mateo or the California for a Coastal Development Permit for at this location?	Coastal Commission
If yes, list Assessor's Parcel	Number(s):	If yes, explain (include date and applic	ration file numbers).
			= =
			(3)
		Buildings or Structure	
			Check if matches existing
<b>Fill in Blanks:</b> a. Exterior Walls	Material STUCCO/HAPPY	Color/Finish GREY   WHITE	
b. Trim	MOOD HUIFFI	WHITE	
c. Roof	MOOD	WHITE	
d. Chimneys	N/A		
e. Accessory Buildings	N/A	Name of the last o	
f. Decks/Stairs	WOOD	STAIN	
a. Retainina Walls	NA		

4. Project Information					,
Does this project, the parcel on which it is loo immediate vicinity involve or include:	cated or	the	p. Between the sea and the nearest public road?		d /
	Yes	No	q. Existing or proposed provisions for public access to the shoreline?		q
a. Demolition of existing housing units? (If yes, give value of owner-occupied		Ø	r. Public or commercial recreation facilities?		<b>1</b>
units or current monthly rent of rental		, , #	s. Visitor-serving facilities?		Ø
units in explanation below.) b. Creeks, streams, lakes or ponds?	airse d	itch.	t. Existing or proposed public trail		/
c. Wetlands (marshes, swamps, mudflats)?			easements?		Ø
d. Beaches?	П		Explain all Yes answers below. Indicate	whethe	r the
e. Sand Dunes?			item applies to the project itself, the parcel on located, or the immediate vicinity (attach addi		
f. Sea cliff, coastal bluffs or blufftops?	П		necessary):		
g. Ridgetops?	П		Two frees (maderey Ane) to Be	1emin	1en
h. Pampas Grass, invasive brooms or			Landscare flow it includ.		1
Weedy Thistle?	_,		Close to a dry drawing of	tel	7
i. Removal of trees or vegetation?	Ø		, ,		
j. Grading or alteration of landforms?		Ø	,		
k. Landscaping?	Ø				
I. Signs?		Ø,			
m. Phone or utility line extensions or connections, either above or below ground (explain which)?		<b>d</b>			
n. Areas subject to flooding?		<b>ø</b> ,			
o. Development on slopes 30% or steeper?					
5. Staff Use Only					
California Coastal Commission Juri	isdictio	on	Commission; a public hearing is always require	ed.	
A. Does the Proposed Project Involve:			<b>B.</b> Does the proposed project involve lands be	elow the	e mean
A subdivision, Certificate of Compliance Type B, Use     Permit, or Planned Agricultural District Permit?			high tide line and lands where the public t (See "Post CCP Certification Permit and App Map).		
☐ Yes ☐ No			☐ Yes ☐ No		
2. Construction or grading within 100 feet of wetland?	a stream	n or			
☐ Yes ☐ No			Yes to above means that the California Coastal		
3. A parcel located between the sea and the through road paralleling the sea; 300 feet fextent of any beach or mean high tide line beach; or within 300 feet of the top of the a coastal bluff?	retains permit jurisdiction over all or part of the project. A Coastal Development Permit from the required.  Reviewed by:				
☐ Yes ☐ No			management Control Control		***************************************
Yes to any one of the above means that the C Development Permit is appealable to the Coa.					

# **Environmental Information Disclosure Form**

Planning and Building Department

PLN 2016-00014

BLD San 1 2016

	isining and vision of
Project Address: NO ADDRESS - VACANT	Name of Owner: PHILOMENA, LCC County  Address: 1580 LAVRELST STE C
HALFMOON BAY, CA 940191	Address: 1580 LAVPELST, STE C
	SAN CATZLOS, CA Phone: 650. 394.2615
Assessor's Parcel No.: $048-054-120$	Name of Applicant: SAME AS ABOVE
$\gamma$ 10000001 31 arcci 110 $\gamma \gamma - \omega \gamma = \gamma 20$	Address:
Zoning District:	Phone:
Zoning Diotrict.	THORE.
Existing Site Conditions	
Parcel size: _5,320 SOFT	
Describe the extent and type of all existing development and u	ses on the project parcel, including the existence and
purpose of any easements on the parcel, and a description of creeks, vegetation).	any natural features on the project parcel (i.e. steep terrain,
Vacant Parcez	
(7 (2 (2 ) ) ) /// ( ) (	
	+41
Environmental Review Checklist	
California Environmental Quality Act (CEQA) F	Doubles
Yes No Will this project involve:	neview
a. Addition to an existing structure > 50% o	
5. Construction of a new multi-family reside	
c. Construction of a commercial structure >	
residential zoning district)?	Emerald Lake Hills area or ≥ 12" d.b.h. in any
If yes, how many trees to be removed?_	Two.
e. Land clearing or grading?	
If yes, please state amount in cubic yards  Excavation:c.y.	ren
f. Subdivision of land into 5 or more parcels	
g. Construction within a State or County sce	
h. Construction within a sensitive habitat?	
Construction within a hazard area (i.e. se	ismic fault, landslide, flood)?
j. Construction on a hazardous waste site (	check with Co. Env. Health Division)?
Please explain all "Yes" answers:,	
Level lot - Toundation work	
text lot - Foundation work	- Gerlan.
(1111) (146)	Je Cy war .

2. Nat	ional M	larine Fisheries Rule 4(d) Review
Yes	No	Will the project involve:
	I,	a. Construction outside of the footprint of an existing, legal structure?
		b. Exterior construction within 100-feet of a stream?
		c. Construction, maintenance or use of a road, bridge, or trail on a stream bank or unstable hill slope?
		d. Land-use within a riparian area?
		e. Timber harvesting, mining, grazing or grading?
		f. Any work inside of a stream, riparian corridor, or shoreline?
		g. Release or capture of fish or commerce dealing with fish?
Please	explain	any "Yes" answers:
	8.	
3. Nat	ional P	ollutant Discharge Elimination System (NPDES) Review
Yes	No	Will the project involve:
		a. A subdivision or Commercial / Industrial Development that will result in the addition or replacement of 10,000 sq. ft. or more of impervious surface?
		If yes, Property Owner may be required to implement appropriate source control and site design measures and to design and implement stormwater treatment measures, to reduce the discharge of stormwater pollutants. Please consult the Current Planning Section for necessary forms and both construction and post-construction requirements.
		ه. Land disturbance of <b>1 acre</b> or more of area?
		If yes, Property Owner must file a Notice of Intent (NOI) to be covered under the statewide General Construction Activities Storm Water Permit (General Permit) <u>prior</u> to the commencement of construction activity. Proof of coverage under State permit must be demonstrated prior to the issuance of a building permit.

#### Certification

I hereby certify that the statements furnished above and in the attached exhibits present the data and information required for this initial evaluation to the best of my ability, and the facts, statements and information presented are true and correct to the best of my knowledge and belief. If any of the facts represented here change, it is my responsibility to inform the County.

Signed: [m] lay, mlafthlum Date: 1/13/16

(Applicant may sign)

#### Miramar Drive Residence

APN: 048-054-120 Half Moon Bay, CA 94019



# FRONT ELEVATION

1/8"=1'-0"

# (SOUTHEAST)



#### **KEYNOTES**


- COMPOSITION SHINGLE ROOF
  CERTAINTEED LANDMARK TL, 'MOIRE BLACK'
- STUCCO WALL WITH PAINTED FINISH
  BENJAMIN MOORE, 'PURITAN GRAY', #HC-164
- HARDIE LAP SIDING W/ PAINTED FINISH BENJAMIN MOORE, 'BOOTHBAY GRAY', #HC-165
- WOOD TRIM / DETAIL WITH STAINED FINISH CABOT STAIN 'FIELDSTONE'
- MOOD DOORS & MINDOMS W METAL CLADDING ANDERSEN (OR EQUAL) WITH "WHITE" FINISH
- 6 WOOD TRIM / DETAIL WITH PAINTED FINISH WHITE! TO MATCH DOOS & WINDOWS
- 1 HALF ROUND GUTTER W ROUND DOWNSPOUTS PAINTED TO MATCH TRIM
- B DOOR WITH STAINED FINISH CABOT STAIN 'FIELDSTONE'
- MALL MOUNTED 'DARK SKY' LIGHT FIXTURE KICHLER LIGHTING #9022WH


#### **EXTERIOR COLORS & MATERIALS**

1



2







3

4

5

- 1. Roof: Composition Shingle, Certainteed Landmark TL, 'Moire Black'
- 2. Walls: Hardie Lap Siding, Painted—Benjamin Moore, 'Boothbay Gray' #HC-165
- 3. Doors & Windows, Trim: Andersen—metal clad, 'White', Painted trim to match
- 4. Stucco Walls: Painted—Benjamin Moore, 'Puritan Gray' #HC-164
- 5. Stained Trim & Front Door: Cabot Stains, "Fieldstone"

Miramar Drive Residence

APN: 048-054-120

Half Moon Bay, California

**KELLOND ARCHITECTS** 



# KICHLER.

Style to live by "



Project

Type

Ordering#

Comments

Seaside Collection Seaside 1 Light Outdoor Wall Lantern in White 9022WH (White)

#### **Product Description:**

With an aura that is as pure as a sea breeze, the Seaside Collection offers the homeowner a unique line of outdoor fixtures guaranteed to bring a new identity to your home's landscape. For this 1-light Seaside Wall Lantern, aluminum with stainless steel is combined with Kichler's White finish, resulting in a high quality fit that will look fantastic for years to come. The fixture houses a 100-watt (max.) bulb that provides outstanding outdoor illumination for your landscape. It is 12" birds is LLL listed for wet location, and is Dark Stice compliant. high, is U.L. listed for wet location, and is Dark Skies compliant.

Available Finishes Black (Painted) Brushed Nickel Olde Brick Olde Bronze White

#### **Technical Information**

Lamp Included:

Not Included

Lead Wire Length:

6"

Extension:

9

Safety Rated:

Wet

HCWO:

Base Backplate:

4.75 X.75

**Dual Mount:** 

Dark Sky:

No

Patent:

Yes

D383239

Light Source:

Incandescent

Socket Base:

Medium

Number of Bulbs: Lamp Type:

Max Watt:

Α

Width:

100W

8"

Height:

12"

Overall Height:

Seaside Collection

Collection: Finish:

White

PROPOSED NEW RESIDENCE

# Miramar Drive Half Moon Bay, CA 94019

APN: 048-054-120

# SHEET INDEX

PROJECT INFO & ARCHITECTURAL SITE PLAN

TOPOGRAPHIC SURVEY

FLOOR PLANS & ROOF PLAN

EXTERIOR ELEVATIONS BUILDING SECTIONS


GRADING & DRAINAGE NOTES

GRADING & DRAINAGE PLAN EROSION CONTROL NOTES & DETAILS

BEST MANAGEMENT PRACTICES

LANDSCAPE PLAN

# PROJECT LOCATION



532 S.F. (10% OF SITE AREA)

# PROJECT DATA

S-17 ZONING 5,320 S.F. SITE AREA

2,819 S.F. (.53 x SITE AREA) ALLOWABLE FLOOR AREA 1,862 S.F. (35% OF SITE AREA) ALLOWABLE COVERAGE

ALLOWABLE IMPERVIOUS

FLOOR AREA 1,462 S.F. FIRST FLOOR 979 S.F. SECOND FLOOR

2,441 S.F. TOTAL 147 S.F. FRONT PORCH & REAR PATIO


2,588 S.F. TOTAL

SITE COVERAGE

1,791 S.F. (1st FLOOR, FRONT PORCH, REAR PATIO, DECK)

IMPERVIOUS SURFACE

523 S.F. (DRIVEWAY, FRONT WALK, DECK STEPS)



# Kellond Architects

14510 Big Basin Way, #205 Saratoga, California 95070

408.741.0600 ph. 408.741.0610 fax

www.kellondarchitects.com

OF THE ARCHITECT.

**PROJECT** 

# Miramar Dr. Residence

APN: 048-054-120 Half Moon Bay, CA 94019

SHEET TITLE

SITE PLAN

**REVISIONS** 

No.	Date	Notes


PROJECT #:

2015.09

DATE: 11 JANUARY 2016


SHEET #:

SD-1










SECOND FLOOR PLAN 3/16"=1'-0"



ROOF PLAN

3/16"=1'-0"

# Kellond Architects

14510 Big Basin Way, #205 Saratoga, California 95070

408.741.0600 ph. 408.741.0610 fax

www.kellondarchitects.com

© ALL DRAWINGS AND WRITTEN MATERIAL HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT, WHICH MAY NOT BE DUPLICATED, USED, OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT.

PROJECT

# Miramar Dr. Residence

APN: 048-054-120 Half Moon Bay, CA 94019

SHEET TITLE

FLOOR PLANS

REVISIONS


No. Date Notes


PROJECT #:

2015.09

DATE: 11 JANUARY 2016


SHEET #: SD-2





3/16"=1'-0"

3/16"=1'-0"



2 SECTION

# Kellond Architects 14510 Big Basin Way, #205 Saratoga, California 95070 408.741.0600 ph. 408.741.0610 fax

© ALL DRAWINGS AND WRITTEN MATERIAL HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT, WHICH MAY NOT BE DUPLICATED, USED, OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT.

#### PROJECT

# Miramar Dr. Residence

APN: 048-054-120 Half Moon Bay, CA 94019

## SHEET TITLE

BUILDING SECTIONS


# REVISIONS

No.	Date	Notes
PRO	IFCT #:	2015 09


PROJECT #: 2015.09

DATE: 11 JANUARY 2016

SHEET #: SD-4



FRONT ELEVATION 3/16"=1'-0" (SOUTHEAST)



REAR ELEVATION 3/16"=1'-0"



SIDE ELEVATION (SOUTHWEST)

3/16"=1'-0"



SIDE ELEVATION (NORTHEAST)

3/16"=1'-0"

## KEYNOTES

- COMPOSITION SHINGLE ROOF
  CERTAINTEED LANDMARK TL, 'MOIRE BLACK'
- 2 STUCCO WALL WITH PAINTED FINISH BENJAMIN MOORE, 'PURITAN GRAY', #HC-164
- HARDIE LAP SIDING W/ PAINTED FINISH
  BENJAMIN MOORE, 'BOOTHBAY GRAY', #HC-165
- 4 WOOD TRIM / DETAIL WITH STAINED FINISH
  CABOT STAIN 'FIELDSTONE'
- 5 MOOD DOORS & WINDOWS W/ METAL CLADDING ANDERSEN (OR EQUAL) WITH WHITE' FINISH
- 6 WOOD TRIM / DETAIL WITH PAINTED FINISH WHITE' TO MATCH DOOS & WINDOWS
- HALF ROUND GUTTER W/ ROUND DOWNSPOUTS
  PAINTED TO MATCH TRIM
- 8 DOOR WITH STAINED FINISH CABOT STAIN 'FIELDSTONE'
- q WALL MOUNTED 'DARK SKY' LIGHT FIXTURE KICHLER LIGHTING #9022WH

PROJECT #:

PROJECT

Miramar Dr.

Residence

Half Moon Bay, CA 94019

EXTERIOR ELEVATIONS

Notes

2015.09

APN: 048-054-120

SHEET TITLE

**REVISIONS** 

Date

DATE: 11 JANUARY 2016


SD-3 SHEET #:

#### **GENERAL NOTES**

- ALL MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE GENERAL AND SPECIFIC PROVISIONS, STANDARD DRAWINGS, AND REQUIREMENTS OF COUNTY OF SAN MATEO.
- CONTRACTOR SHALL SECURE A STREET OPENING PERMIT FROM THE COUNTY ENGINEERING DEPARTMENT AND PAY APPROPRIATE FEE PRIOR TO COMMENCEMENT OF WORK. ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE DONE UNDER A SINGLE STREET OPENING PERMIT.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION OF ALL EXISTING UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. CONTRACTOR SHALL NOTIFY ALL PUBLIC AND PRIVATE UTILITY OWNERS 48 HOURS PRIOR TO COMMENCEMENT OF WORK ADJACENT TO THE UTILITY CONTACT UNDERGROUND SERVICE ALERT (USA) AT 800/642-2444.
- EXISTING UTILITIES SHOWN ARE BASED UPON RECORD INFORMATION AND ARE APPROXIMATE IN LOCATION AND DEPTH. THE CONTRACTOR SHALL POTHOLE ALL EXISTING UTILITIES THAT MAY BE AFFECTED BY NEW FACILITIES IN THIS CONTRACT. VERIFY ACTUAL LOCATION AND DEPTH, AND REPORT POTENTIAL CONFLICTS TO THE ENGINEER PRIOR TO EXCAVATION FOR NEW
- IT IS THE CONTRACTORS RESPONSIBILITY TO REPLACE ALL STREET MONUMENTS, LOT CORNER PIPES, AND GRADE STAKES DISTURBED DURING THE PROCESS OF CONSTRUCTION AT THE REGULAR ENGINEER'S FEE.
- PROVIDE CONCRETE PROTECTION BETWEEN UNDERGROUND PIPE CROSSINGS WITH 12" OR LESS VERTICAL CLEARANCE.
- ALL SURPLUS AND UNSUITABLE MATERIAL SHALL BE REMOVED FROM PROJECT SITE AND FROM PUBLIC RIGHT-OF-WAY.
- CONTRACTOR SHALL PROVIDE ADEQUATE DUST CONTROL AND KEEP MUD AND DEBRIS OFF THE PUBLIC RIGHT-OF-WAY AT ALL TIMES.
- ALL TRENCHES AND EXCAVATIONS SHALL BE CONSTRUCTED IN STRICT COMPLIANCE WITH THE APPLICABLE SECTIONS OF CALIFORNIA AND FEDERAL O.S.H.A. REQUIREMENTS AND OTHER APPLICABLE SAFETY ORDINANCES. CONTRACTOR SHALL BEAR FULL RESPONSIBILITY FOR TRENCH SHORING DESIGN AND INSTALLATION.
- GRADE BREAKS ON CURBS AND SIDEWALKS ARE TO BE ROUNDED OFF ON FORM WORK AND FINISHED SURFACING.
- CONTRACTOR SHALL PERFORM HIS CONSTRUCTION AND OPERATION IN MANNER WHICH WILL NOT ALLOW HARMFUL POLLUTANTS TO ENTER THE STORM DRAIN SYSTEM. TO ENSURE COMPLIANCE, THE CONTRACTOR SHALL IMPLEMENT THE APPROPRIATE BEST MANAGEMENT PRACTICE (BMP) AS OUTLINED IN THE BROCHURES ENTITLED BEST MANAGEMENT PRACTICES FOR THE CONSTRUCTION INDUSTRY" ISSUED BY THE SAN MATEO COUNTYWIDE STORM WATER POLLUTION PREVENTION PROGRAM, TO SUIT THE CONSTRUCTION SITE AND JOB CONDITION, THE CONTRACTOR SHALL PRESENT HIS PROPOSED BMP AT THE PRECONSTRUCTION MEETING FOR DISCUSSION AND APPROVAL.
- OVERNIGHT PARKING OF CONSTRUCTION EQUIPMENT IN THE STREET RIGHT-OF-WAY SHALL NOT BE PERMITTED, EXCEPT AT LOCATION(S) APPROVED BY THE COUNTY.
- THE CONTRACTOR SHALL OBTAIN AN ENCROACHMENT PERMIT FROM THE COUNTY'S ENGINEERING DIVISION FOR ALL WORK WITHIN THE PUBLIC RIGHT OF WAY
- THE STORM RUNOFF GENERATED BY THE NEW PROJECT SHALL NOT DRAIN ONTO ADJACENT PROPERTIES. THE EXISTING STORM DRAINAGE FROM THE ADJACENT PROPERTIES SHALL NOT BE BLOCKED BY THE NEW DEVELOPMENT.

#### **GRADING NOTES**

- CONTRACTOR SHALL CONTACT U.S.A. AT LEAST 48 HOURS PRIOR TO EXCAVATING IN ANY AREA WHERE UNDERGROUND FACILITIES ARE LOCATED. PHONE (800)642-2444.
- 2. THE EXISTENCE, LOCATION AND ELEVATION OF ANY UNDERGROUND UTILITIES ARE SHOWN IN A GENERAL WAY ONLY. IT WILL BE THE RESPONSIBILITY AND DUTY OF THE CONTRACTOR TO MAKE FINAL DETERMINATIONS AS TO THE EXISTENCE, LOCATION AND ELEVATION OF ALL UTILITIES.
- 3. THE SITE SHALL BE CLEARED OF ALL EXISTING STRUCTURES, CONCRETE FOOTINGS, PAVEMENT, LANDSCAPING MATERIALS AND UNDERGROUND UTILITIES.
- 4. FINISHED GRADES ALONG THE PERIMETER OF THE FOUNDATION TO BE SLOPED AT A MINIMUM OF 5% FOR FIRST 5 FEET.
- 5. ALL CONCRETE SHALL BE CLASS "A" CONFORMING TO SECTION 90 OF CALTRANS SPECIFICATIONS AND SHALL DEVELOP A COMPRESSIVE STRENGTH OF 3,000 PSI AT 28 DAYS PER CALIFORNIA TEST METHOD NO. 521.
- 6. ASPHALT CONCRETE PAVEMENT SHALL BE TYPE B, 3/4" MAXIMUM, MEDIUM WITH SLURRY SEAL COAT. ASPHALT CONCRETE SHALL BE PLACED IN ONE OR MORE LIFTS TO THE MINIMUM TOTAL THICKNESS SHOWN ON THE PLANS. THE MAXIMUM THICKNESS OF EACH LIFT SHALL NOT EXCEED THREE (3) INCHES.
- 7. AGGREGATE BASE SHALL BE PLACED BENEATH ALL SIDEWALK, CURB AND GUTTER, AND ASPHALT CONCRETE PAVEMENT AS SHOWN ON THE PLANS. AGGREGATE BASE SHALL BE CLASS 2, 1-1/2" MAXIMUM COMPACTED TO AT LEAST 95" RELATIVE COMPACTION PER ASTM D1557-91
- 8. ON-SITE UTILITY TRENCHES SHALL BE BACKFILLED WITH COMPACTED ENGINEERED FILL. THE FILL MATERIAL SHALL BE PLACED IN LIFTS NOT TO EXCEED EIGHT (8) INCHES IN UNCOMPACTED THICKNESS AND SHALL BE MECHANICALLY COMPACTED TO AT LEAST 90% RELATIVE COMPACTION.
- 9. ALL UTILITIES SHALL BE UNDERGROUND FROM THE PROPERTY LINES IN. LOCATION OF METERS ARE AS NOTED. COORDINATE ALL SUCH WORK WITH THE UTILITY COMPANY HAVING JURISDICTION.
- 10. STORM DRAIN POLLUTION PREVENTION. PROTECT DOWNSLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH HAY BALES. TEMPORARY DRAINAGE SWALES, SILT FENCES, BERMS OR STORM DRAIN INLET FILTERS COVER STOCK PILES AND EXCAVATED SOIL WITH SECURED TARPS OR PLASTIC SHEETING.
- 11. CONTACT PUBLIC WORKS TO SCHEDULE AN INSPECTION A MINIMUM OF 24 HOURS IN ADVANCE OF COMMENCEMENT OF PUBLIC IMPROVEMENT WORK TO SCHEDULE A PRE-CONSTRUCTION MEETING AND FOR EACH SUBSEQUENT DAY OF WORK IN THE PUBLIC RIGHT OF WAY.
- 12. ALL EXISTING FRONTAGE IMPROVEMENTS (CURB, GUTTER, SIDEWALK, VALLEY GUTTER, PARKING STRIP) THAT ARE DAMAGE DURING THE COURSE OF CONSTRUCTION MUST BE REPAIRED TO "AS NEW" CONDITION. COUNTY WILL NOT BEAR THE COSTS OF RECONSTRUCTION.
- 13. ALL WORK WITHIN THE PUBLIC RIGHT OF WAY SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF THE COUNTY OF SAN MATEO STANDARD DETAILS. ALL DETAILS APPLICABLE TO THE PARTICULAR CONSTRUCTION ACTIVITY SHALL BE UTILIZED.
- 14. ALL IMPROVEMENTS IN THE PUBLIC RIGHT OF WAY ARE TO BE COMPLETED AND APPROVED BY THE CONSTRUCTION SUPERVISOR PRIOR TO FINAL INSPECTION BY THE BUILDING INSPECTOR.
- 15. DATE OF SURVEY: OCT. 2015
- 16. ALL GRADING DURING THE RAINY SEASON (OCT. 1ST THROUGH APRIL 30TH) REQUIRES AND EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE CITY. STORMWATER POLLUTION PREVENTION MEASURES SHALL BE IMPLEMENTED THROUGHOUT THE YEAR, TO THE SATISFACTION OF THE CONSTRUCTION SUPERVISOR.
- 17. ALL CHANGES TO THE APPROVED GRADING AND DRAINAGE PLAN REQUIRE A PLAN MODIFICATION APPROVAL BY THE COUNTY IN ADVANCE OF CONSTRUCTION THE CHANGE. THE PROPOSED PLAN CHANGE MUST BE GENERATED FROM THE ENGINEER / ARCHITECT WHO ORIGINALLY PREPARED THE PLAN.
- 18. ANY DEVIATION FROM THE APPROVED PLAN AND/OR FAILURE TO OBTAIN GRADING AND DRAINAGE INSPECTION MAY AFFECT THE PUBLIC WORKS SIGN-OFF FOR BUILDING FINAL AND/OR OCCUPANCY.



NOTE: WATER RETENTION CAPACITY OF BED IS LIMITED TO 40% OF TOTAL BED VOLUME.

DRAIN ROCK RETENTION BASIN SCALE: V: 1"=2' H: 1"=1'

VOLUME OF DRAIN ROCK USE 10' X 11' FOOTPRINT VOL OF BOTTOM LAYER DRAIN ROCK=10'X11'X2'=220CF VOL OF DRAIN ROCK ON SIDES OF CB ABOVE BOTTOM LAYER =((10'X10')-4SF)X2.5'=240CF

VOLUME OF DRAIN ROCK REQUIRED PER CALCULATIONS

TOTAL VOLUME OF DRAIN ROCK=440CF

#### **ABBREVIATIONS**

ASPHALT CONCRETE APN ASSESSORS PARCEL NUMBER BLD BUILDING CATCH BASIN CLEAN OUT CONC CONCRETE CONTROL POINT DS DOWN SPOUT DWY DRIVEWAY EXISTING EX ELECTRICAL METER FACE OF CURB FINISH FLOOR FINISH GRADE FIRE HYDRANT GAS/GROUND GM GAS METER PIPE INVERT JOINT POLE

LIGHT WELL

BOTTOM OF SILL TO ADJ. SOIL

FINISHED

ON-SITE ONLY

GRADE

MAN HOLE MON MONUMENT NEW PROPERTY LINE PARCEL MAP PAVEMENT PVMT ROOF DRAIN TOP OF GRATE RIM STORM DRAIN SD STORM DRAIN MANHOLE SANITARY SEWER SANITARY SEWER CLEANOUT S/W SIDEWALK TEMPORARTY BENCH MARK TBM VALLEY GUTTER WATER WOOD FENCE WDF


WATER METER

WATER VALVE

SEE STRUCTURE PLANS FOR

SCALE: N.T.S

STRUCTURAL DESIGN



#### VICINITY MAP N.T.S **LEGEND**

DESCRIPTION

PROPERTY LINE

STORM DRAIN

DOWN SPOUT

CATCH BASIN (CB)

AREA DRAIN (AD)

FIBER ROLL

MIRAMAR DRIVE

FILL SOIL

TOM CAREY

CIVIL ENGINEER BAY LAND CONSULTING

KELLOND ARCHITECTS

SARATOGA, CA 95070

CIVIL ENGINEERS

P.B BOX 299

PAT MCNULTY

1604 FRANCIS AVE.

BELMONT, CA 94002

14510 BIG BASIN WAY, #205

Santa Clara, California 95050

AC PAVEMENT DWY.

CONCRETE/ HARDSCAPE

OR ON-SITE GRAVEL PATH

GAS


WATER

SANITARY SEWER

EXISTING PROPOSED

CONCEPTUAL PERIMETER FOOTING-TYPE 1 CLEARANCE FROM ADJACENT SOIL

SEE STR. & ARCH. PLANS SCALE: N.T.S ON-SITE ONLY



CONCEPTUAL PERIMETER FOOTING-TYPE 2 CLEARANCE WITH CONCRETE APRON SEE STR. & ARCH. PLANS

ALL WORK TO BE COMPLETED IN CONFORMANCE WITH THE GEOTECHNICAL INVESTIGATION PREPARED BY BUCKLEY ENGINEERING ASSOCIATES, INC., FILE NO. 11318.27, JUNE 30, 2014. PHONE 408-966-6680

ESTIMATED EARTHWORK QUANTITIES

LESS THAN 30 C.Y. FILL LESS THAN 10 C.Y. CUT (EXCLUDES BASEMENT EXCAVATION) ESTIMATE ASSUMES A 15% COMPACTION FACTOR ON ALL FILL MATERIAL AND A 0% COMPACTION FACTOR ON ALL CUT MATERIAL. ESTIMATE DOES NOT INCLUDE VOLUMES FOR CLEARING AND GRUBBING. ALL TOPSOIL FROM CUT CAN BE USED IN TOP 1' OF LANDSCAPE. CONTRACTOR TO MAKE OWN ESTIMATES OF QUANTITIES FOR BIDDING PURPOSES BASED ON ALL PLANS.

## FOR PLAN CHECK ONLY

These plans are for "plan check only" and as such the State of California Business and Professional Code, Professional Engineers Act Section 6735(a) does not require the plans to be wet stamped and signed. These plans are not final until they are approved for permit at which time they will be wet stamped and signed.



# SHEET INDEX

OWNER

ARCHITECT

SURVEYOR

C1 NOTES & DETAILS C2 GRADING AND DRAINAGE PLAN C3 EROSION CONTROL NOTES & DETAILS C4 BEST MANAGEMENT PRACTICES PLAN

S

O

Ö

Z

 $\mathbf{m}$ 

Z ORP ORP  $\overline{\forall}$ Z Z  $\triangleleft$  $\triangleleft$ MIR

 $\triangleleft$ 

0

2

0

4

PN

V

>0 ADING NOTES  $\triangleleft$ GR 0 0

REVISIONS DESCRIPTION

JOB NO. 15012

SCALE: AS SHOWN DRAWN BY: YC CHECKED BY: SH

DATE: 01/11/16

SHEET

OF 4 SHEETS

2.) The Elevations shown are based upon an assumed Datum.

survey. Any Site Plan or Grading Plan has been

1.) Survey shows existing site conditions at the time of the

LOT AREA

PROJECT BENCHMARK

The top of a 1" Iron Pipe found at the

property corner was used as the Datume

Point for this survey. Elevation = 58.49

SURVEY NOTES

5320.0 sq. ft.+/-

(Assumed Datum)


done by others.

#### STANDARD NOTES EROSION CONTROL PLAN

- OWNER: TOM CAREY IT SHALL BE THE OWNER'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THE SOIL EROSION CONTROL MEASURES.
- 2. CIVIL ENGINEER: SCOTT HOFFMAN BAY LAND CONSULTING 2005 DE LA CRUZ BLVD. STE 165, SANTA CLARA, CA PH: 408-296-6000. EMAIL: scott@ah-land.com
- 3. PERFORM CLEARING AND EARTH-MOVING ACTIVITIES ONLY DURING DRY WEATHER. MEASURES TO ENSURE ADEQUATE EROSION AND SEDIMENT CONTROL SHALL BE INSTALLED PRIOR TO EARTH-MOVING ACTIVITIES AND CONSTRUCTION.
- 4. MEASURES TO ENSURE ADEQUATE EROSION AND SEDIMENT CONTROL ARE REQUIRED YEAR-ROUND. STABILIZE ALL DENUDED AREAS AND MAINTAIN EROSION CONTROL MEASURES CONTINUOUSLY BETWEEN OCTOBER 1 AND APRIL 30.
- 5. STORE, HANDLE, AND DISPOSE OF CONSTRUCTION MATERIALS AND WASTES PROPERLY, SO AS TO PREVENT THEIR CONTACT WITH STORMWATER.
- 6. CONTROL AND PREVENT THE DISCHARGE OF ALL POTENTIAL POLLUTANTS , INCLUDING PAVEMENT CUTTING WASTES, PAINTS, CONCRETE, PETROLEUM PRODUCTS, CHEMICALS, WASH WATER OR SEDIMENTS, AND NON-STORMWATER DISCHARGES TO STORM DRAINS AND WATERCOURSES.
- 7. AVOID CLEANING, FUELING, OR MAINTAINING VEHICLES ON—SITE, EXCEPT IN A DESIGNATED AREA WHERE WASH WATER IS CONTAINED AND TREATED.
- 8. LIMIT AND TIME APPLICATIONS OF PESTICIDES AND FERTILIZERS TO PREVENT POLLUTED RUNOFF.
- 9. LIMIT CONSTRUCTION ACCESS ROUTES TO STABILIZED, DESIGNATED ACCESS POINTS.
- 10. AVOID TRACKING DIRT OR OTHER MATERIALS OFF-SITE: CLEAN OFF-SITE PAVED AREAS AND SIDEWALKS USING DRY SWEEPING METHODS.
- TRAIN AND PROVIDE INSTRUCTION TO ALL EMPLOYEES AND SUBCONTRACTORS REGARDING THE WATERSHED PROTECTION MAINTENANCE STANDARDS AND CONSTRUCTION BEST MANAGEMENT PRACTICES.
- 12. CONSTRUCTION SITES ARE REQUIRED TO HAVE EROSION CONTROL MATERIALS ON-SITE DURING THE "OFF-SEASON."
- 13. DUST CONTROL IS REQUIRED YEAR-ROUND.
- 14. EROSION CONTROL MATERIALS SHALL BE STORED ON-SITE.
- 15. USE OF PLASTIC SHEETING BETWEEN OCTOBER 1ST AND APRIL 30TH IS NOT ACCEPTABLE, UNLESS FOR USE ON STOCKPILES WHERE THE STOCKPILE IS ALSO PROTECTED WITH FIBER ROLLS CONTAINING THE BASE OF THE STOCKPILE.
- 16. THE TREE PROTECTION SHALL BE IN PLACE BEFORE ANY GRADING, EXCAVATING OR GRUBBING IS STARTED.
- 17. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT.
- 18. THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. NOTIFY THE COUNTY REPRESENTATIVE OF ANY FIELD CHANGES.

#### MAINTENANCE NOTES

- MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:
- A. REPAIR DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION AT THE END OF EACH WORKING DAY.
- SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
- C. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
- D. SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1 FOOT.
- E. SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
- RILLS AND GULLIES MUST BE REPAIRED.
- 2. SAND BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE SAND BAG.



EXISTING GROUND

ON SLOPES

ON LEVEL GROUND

1. PLACE STRAW ROLL IN TRENCH EXCAVATED 3" (0.024')

2. ON SLOPES PLACE ROLL TO FOLLOW THE CONTOUR AS

CLOSELY AS POSSIBLE. CURVE ENDS UPHILL AT THE

ALLOWED TO RUN UNDER OR AROUND ROLL ..


3. ABUT ADJACENT ROLLS TIGHTLY.

SCALE: NTS


INTO GROUND ALONG CONTOUR. RUNOFF MUST NOT BE

STRAW ROLL OR

FIBER ROLL



SECTION IPU-1 NOT TO SCALE




MIRAFI 2000 FILTER FABRIC UNDER GRATE STRAW ROLL

NOTE: MAX. DEPTH OF BED IS LIMITED TO 2FT & BED MUST BE LOCATED AT LEAST 10FT AWAY FROM NEAREST PROPERTY LINE & TREE.

EST. DIMENSIONS OF GRAVEL BED: WIDTH = 4FT

LENGTH = 4FT PER DETAIL BELOW DEPTH = 2 FT —

INLET PROTECTION IN UNPAVED AREAS SCALE: NTS




BRING THE DISTURBED AREA TO THE GRADE OF THE DROP INLET AND SMOOTH AND COMPACT IT. APPROXIMATELY STABILIZE ALL BARE AREAS AROUND THE INLET.

PROPERLY DISPOSE OF ACCUMULATED SEDIMENT

INSPECT ALL INLET PROTECTION DEVICES BEFORE AND AFTER RAINFALL EVENTS, AND WEEKLY THROUGHOUT THE RAIN SEASON. DURING EXTENDED RAINFALL EVENTS, INSPECT INLET PROTECTION DEVICES AT LEAST ONCE EVERY 24 HOURS.

REMOVE ALL INLET PROTECTION DEVICES WITHIN THIRTY DAYS AFTER THE SITE IS STABILIZED, OR WHEN INLET PROTECTIONS IS NO LONGER REQUIRED.



#### CATCH BASIN INLET FILTER

# INSTALLATION REMOVE DRAIN GRATE

REPLACE GRATE TO BASIN THEREBY PINCHING FABRIC BETWEEN GRATE AND CATCH BASIN AND HOLDING FILTER IN PLACE


#### INSPECTION AND MAINTENANCE

EMPTY CATCH BASIN FILTERS WHEN

DISPOSE OF TRAPPED SEDIMENT IN ACCORDANCE WITH LOCAL

DISCARD AND REPLACE AS NECESSARY

STORM DRAIN INLET PROTECTION PUBLIC STREET




INSERT CATCH BASIN FILTER INTO BASIN LEAVING 3" FLAP EXPOSED


INSPECT CATCH BASIN FILTERS WEEKLY AND AFTER EVERY RAIN

FILTERS APPEAR TO BE HALF FULL

REQUIREMENTS

CLEAN AND REUSE INLET FILTERS OR







CONSUL

AND

a

OR Z ID DRAIP NOTES R DRIVE MAR UNIN 48-( ADING AN CONTROL RAM, Y(UN MIR. BAY BA O 0  $\geq$ 0 R AL Ш 工

2

0

REVISIONS DATE | DESCRIPTION


JOB NO. 15012

SCALE: AS SHOWN DRAWN BY: YC CHECKED BY: SH

SHEET

DATE: 01/11/16

OF 4 SHEETS



REFERENCE NOTES:

- (1.) INSTALL AREA DRAINS ALONG SIDE YARD, SEE TYP. DETAIL
- 2. NEW 4" STORM DRAIN @ 2% MIN. PVC SCH 40 SDR 26 MIN.
- 3. INSTALL NEW 4" SEWER @2% MIN. SLOPE. SDR 35 MIN. PIPE PER SEPARATE PERMIT WITH GRANADA SANITARY DISTRICT
- 4.) FOR THE COUNTY STANDARD DRIVEWAY APPROACH, INTALL SLIGHT DRAINAGE SWALE PER DIRECTION OF ROAD INSPECTOR.

NOIL

 $\dot{\mathcal{O}}$ 

CONSTRU

OR

0

ONL

SU

Z

Z

CONSUL

0 ORATED DRIVE SORP Y(UNIN( 048-0 MIR, BAY Z O 0

DATE | DESCRIPTION

JOB NO. 15012 SCALE: AS SHOWN DRAWN BY: YC CHECKED BY: SH DATE: 01/11/16

SHEET

OF 4 SHEETS

Lot 8 Block 1 of R.S.M. Book 4 of Maps pg. 12 SITE ADDRESS: Vacant Lot Miramar Drive,

PANEL 255 OF 510 DATE: OCTOBER 16, 201.

SURVEY COMPLETED BY PAT MCNULTY PROFEESIONAL LAND SURVEYOR 1604 FRANCIS AVENUE

BELMONT, CA 94002 TEL: 650-654-6460

FEMA FLOOD ZONE: ZONE X

Unincorporated San mateo County A.P.N. 048-054-120 Area = 5320.0 sq. ft.+/-

done by others.

The top of a 1" Iron Pipe found at the property corner was used as the Datume Point for this s Elevation = 58.49 (Assumed Datum)

INSTALL INLET PROTECTION AT NEAREST DOWNSTREAM INLET, DETAIL

Survey shows existing site conditions at the time of the survey. Any Site Plan or Grading Plan has been


2.) The Elevations shown are based upon an assumed Datum.

# Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

Clean Water. Healthy Community.

# **Materials & Waste Management**



#### Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- ☐ Use (but don't overuse) reclaimed water for dust control.

#### **Hazardous Materials**

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

#### Waste Management

- Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ☐ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ☐ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- ☐ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

#### **Construction Entrances and Perimeter**

- Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

# **Equipment Management & Spill Control**




#### Maintenance and Parking

- ☐ Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

#### Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up spills or leaks immediately and dispose of cleanup materials properly.
- ☐ Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- ☐ Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

# **Earthmoving**




- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

#### **Contaminated Soils**

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or trash.

Storm drain polluters may be liable for fines of up to \$10,000 per day!


# Paving/Asphalt Work



- Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- ☐ Do not use water to wash down fresh asphalt concrete pavement.

#### Sawcutting & Asphalt/Concrete Removal


- ☐ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ☐ Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!)
- ☐ If sawcut slurry enters a catch basin, clean it up immediately.



Concrete, Grout & Mortar


- ☐ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as
- ☐ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

# Landscaping




- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.

# **Painting & Paint Removal**



#### **Painting Cleanup and Removal**

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a statecertified contractor.



- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant.
- ☐ Divert run-on water from offsite away from all disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ☐ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal.



Z CTICE

PRA( DRIVE JG JAGEN MIRA BAY

MANA O 0 Ш

**ADING** 

GR

REVISIONS DATE | DESCRIPTION

JOB NO. 15012 SCALE: AS SHOWN

DRAWN BY: YC CHECKED BY: SH

SHEET

DATE: 01/11/16

OF 4 SHEETS

# EXT'G SOLID WOOD -WILDFLOWER SEED MIXTURE NEW 6' HIGH SOLID WOOD FENCE ESCA RUB DECK MYR CAL PATIO DINING 125 X 155 BARK CHIPS -BUILDING UNDER CONSTRUCTION - BARK CHIPS EX 36" PINE PORCH TO BE REMOVED -EXT'G CYPRESS GARAGE TREES TO REMAIN, -APPROX. 48" BOX SIZE EACH MYR CAL PEN SET EX 20" PINE TO BE REMOVED -ARB 'MAR' **BUD DAV** DOD VIS CONCRETE DRIVEWAY CEA GRI BENCH MARK: EX 32" PINE TO REMAIN -The top of a 1" Iron Pipe found at the property corner was used as the Datume Point for this survey. Elevation = 58.49 (Assumed Datum) PEN SET SOL HET ERIG KAR CEA GRI MIRAMAR DRIVE

# **Plant List**

No.	Botanical Name	Common Name	Qty	Size	Remarks
ARB MAR	Arbutus 'Marina'	Strawberry Tree	1	15 Gal	Evgn Tree
BUD DAV	Buddleia davidii	Butterfly Bush	1	5 Gal	Evgn Shrub
DOD VIS	Dodonaea viscosa	Hopseed Bush	3	5 Gal	Evgn Shrub
ERIG KAR	Erigeron karvinskianis	Santa Barbara Daisy	18	1 Gal	Low Shrub
ESCA RUB	Escallonia rubra	Red Escallonia	3	5 Gal	Evgn Shrub
HEM SPP	Hemerocallis 'Yellow'	Daylily	18	1 Gal	Low Shrub
MYR CAL	Myrica californica	Pacific Wax Myrtle	32	5 Gal	Evgn Shrub
PEN SET	Pennisetum setaceum	Red Fountain Grass	3	5 Gal	Grassy Plant
RHAP	Rhapiolepsis indica	Indian Hawthorn	4	5 Gal	Evgn Shrub
bootstaat valitatikkelitan onte on taal Piologie 1965, tatooriaa 2017 vantui	'Ballerina'			004	
SOL HET	Sollya heterophylla	Australian Bluebells	18	1 Gal	Low Shrub
CEA GRI	Ceanothus griseus	Carmel Creeper	15	1 Gal	Groundcover
ako z uranjeto su preded k dilizion, k č izi die klovij dela a <del>oddi</del> si nav (ene v čim. i	'Horizontalis'			The state of the s	

Note 1. Contractor shall verify quantites


Note 2. 80% of all plant materials shall be LOW in water consumption per 2013 WUCOLS list.

# **PLANTING NOTES**

- 1. CONTRACTOR SHALL CONTACT UNDERGROUND SERVICES ADMINISTRATION PRIOR TO **EXCAVATION AND GRADING.**
- 2. ALL PLANTING AREAS SHALL BE CLEARED OF WEEDS AND OTHER DEBRIS. THE CONTRACTOR SHALL VERIFY WITH THE OWNER WHICH EXISTING PLANTS ARE TO REMAIN. EXISTING PLANTS TO BE REMOVED SHALL BE VERIFIED WITH OWNER PRIOR TO REMOVAL. ALL IVY IN PROJECT AREA SHALL BE REMOVED; IVY SHALL BE SPRAYED WITH HERBICIDE TWO WEEKS PRIOR TO REMOVAL.
- SOIL TESTING SHALL BE UNDERTAKEN BY THE CONTRACTOR, AND PERFORMED BY A CERTIFIED LABORATORY. A COPY OF THE REPORT SHALL BE PROVIDED TO THE OWNER AND LANDSCAPE ARCHITECT. RECOMMENDATIONS FOR AMENDMENTS AND FERTILIZATION SHALL REFLECT THE NUTRIENT REQUIREMENTS OF SPECIFIED PLANT SPECIES.
- 4. SOIL AMENDMENTS SHALL BE FREE OF DEBRIS SUCH AS LITTER, BROKEN CLAY POTS, AND OTHER FOREIGN MATERIAL. ROCKS LARGER THAN ONE INCH DIAMETER WILL NOT BE PERMITTED. SOIL AMENDMENTS SHALL HAVE THE FOLLOWING CONTENT: REDWOOD NITRIFIED COMPOST 40%, COARSE SAND 30%, BLACK TOPSOIL 30%.
- 5. PLANT HOLES SHALL BE DOUBLE THE SIZE OF THE CONTAINER (generally). THE WALLS AND BASES OF PLANT HOLES SHALL BE SCARIFIED. HOLES SHALL BE BACKFILLED WITH THE FOLLOWING MIXTURE: 80% TO 20% IMPORTED SOIL TO EXISTING SOIL.
- 6. SOIL BERMS SHALL BE FORMED AROUND ALL PLANTS 1 GALLON SIZE AND LARGER. BASINS SHALL BE MULCHED WITH A 2" LAYER OF BARK CHIPS, MINIMUM OF 1" IN SIZE. PLANTING AREAS SHALL BE COVERED WITH A TWO INCH LAYER OF BARK CHIPS.
- 7. ALL PLANTS SHALL BE FERTILIZED. FERTILIZER SHALL BE COMMERCIALLY AVAILABLE TYPE, AGRIFORM OR EQUIVALENT. APPLICATION SHALL BE ACCORDING TO MANUFACTURER'S INSTRUCTIONS. RESIDUAL WEED PRE-EMERGENT SHALL BE APPLIED BY THE CONTRACTOR. APPLICATION SHALL BE ACCORDING TO MANUFACTURER'S INSTRUCTIONS.
- 8. TREES SHALL BE STAKED WITH TWO PRESSURE TREATED 2" DIAMETER POLES. TREE TRUNK SHALL BE SECURED WITH TWO RUBBER TIES OR STRAPS FORMING A FIGURE-EIGHT BETWEEN TRUNK AND STAKE.

# **PLANTING PLAN**

1/8"=1'-0"





# Land Planning Concepts

Landscape Architect Reg. 2324

923 Arguello Street, Suite 200 Redwood City, California 94063

Tel (650) 346-7645 Fax (650) 367-8139 Email: bacla@sbcglobal.net

# Miramar Drive Residence

APN: 048-054-120 Half Moon Bay, CA 94019

SHEET TITLE

Landscape Plan

**REVISIONS** 

Date Notes

PROJECT #:

DATE: 1-13-16

SHEET #: